



BILL OF MATERIALS	
ITEM	QUANTITY
① 4" - 10" WATER MAIN	PER PLAN
② 4" - 10" MJ END CAP W/ 2" ECCENTRIC TAP	1
③ 2" x 12" GALV STEEL PIPE, (IPT)	2
④ 2" GALV STEEL PIPE, (IPT)	6 LF ±
⑤ 2" VALVE (FIPT), PER SPECIFICATIONS	1
⑥ 2" x 90° GALV STEEL ELL, (FIPT)	2
⑦ 2" GALV END CAP, (FIPT)	1
⑧ MAIN SIZE GRIP RING KIT	1
⑨ METER BOX (TRAFFIC RATED LID AND BOX)	1

NOTES:
 1.) CONTRACTOR SHALL LEAVE END CAP IN PLACE UNTIL FINAL CONNECTION BY CITY FORCES



WATER DISTRIBUTION & TRANSMISSION PIPELINE CONSTRUCTION METHODS

4" THROUGH 10" TEMPORARY CONSTRUCTION END CAPS FOR FLUSHING, TESTING, & CHLORINATION